

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Huntington

WELL NUMBER 2

 Ft. from S Section Line

SW $\frac{1}{4}$ Ft. from E Section Line

SEC. 7 TWP. 7 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 6-3-78

Plugging Commenced 4-19-93

Plugging Completed 4-19-93

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-19-93 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3861

Show depth and thickness of all water, oil and gas formations.

PBTD 3750

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	260	8 5/8		None
	Casing	0	3861	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pulled tubing and packer. Hook to 5 1/2 casing pump 210 sk. 65/35 pos with 10% gel and 500# pills. Max pressure 1300# Shut in. Hook to 8 5/8 and mix 30 sk. cement coming out of ground. Shut in 0#.

Name of Plugging Contractor Beren Corp. License No. 5364

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beren Corp.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Mo 67601

NOTARY PUBLIC-State of Kansas
 ROSEMARY SMITH
 My Appl. Exp: 5-1-1995

SUBSCRIBED AND SWORN TO before me this 22 day of April 19 93

Rosemary Smith
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

My Commission Expires: 5-1-1995
 USE ONLY ONE SIDE OF EACH FORM

APR 23 1993

Form CP-4
 CORRELATION DIVISION
 Wichita, Kansas

4-23-1993