

15-065-30358-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Graham County, Sec. 7 Twp. 7S Rge. 25 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW NW NE

Lease Owner Halliburton Oil Producing Company

Lease Name Best Well No. 1

Office Address Cameron Building, 2915 Classen Blvd, Oklahoma City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 2 19 66

Application for plugging filed January 2 19 66

Application for plugging approved January 2 19 66

Plugging commenced January 2 19 66

Plugging completed January 2 19 66

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	290	7"	290	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged with 15 sx cement @ 540'; 15 sx cement @ 275';  
10 sx cement @ 40' to surface.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 11 1966

1-11-66

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Paine Drilling Co., Inc.

Address P. O. Box D, Hill City, Kansas

STATE OF Kansas, COUNTY OF Graham, ss.

D. F. McCarthy

(employee of owner or lessee or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

D. F. McCarthy

P. O. Box D, Hill City, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 66

My Commission Expires January 20, 1968

My commission expires \_\_\_\_\_

Carla Drexler

Notary Public.

15-065-30358-00-00

CONTRACTOR'S WELL LOG

COMPANY: Halliburton Oil Producing Company  
 CONTRACTOR: Paine Drilling Co., Inc.  
 WELL: Best # 1  
 LOCATION: SW NW NE Section 7-78-25W  
 Graham County, Kansas  
 COMMENCED: December 22, 1965  
 COMPLETED: January 2, 1966

0	440	Sand & Shale
440	1070	Shale
1070	1140	Shale & Pyrite
1140	1734	Shale, Sand & Pyrite
1734	1910	Sand
1910	2124	Shale
2124	2158	Anhydrite
2158	2682	Shale
2682	3575	Shale & Lime
3575	3850	Lime & Shale
3850		Rotary Total Depth

RECEIVED  
 STATE COMMISSION  
 JAN 11 1966  
 1-11-66

Set 7-inch surface casing @ 290 ft. with 250 sx cement.

Dry & Abandoned

We hereby certify that the above is a correct and accurate log of the above mentioned well, as shown on the daily drilling reports.

PAINE DRILLING CO., INC.

BY: A. J. McCarthy  
 Treasurer

Subscribed and sworn to before me this 5th day of January, 1966.

My Commission Expires January 22, 1966

Carroll Pessler  
 Notary Public