


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-065-00186-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 15 Twp. 7 Rge. (E) 25 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE
Lease Owner Harry Gore
Lease Name Moore Well No. 1
Office Address 400 Brown Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-18-51 19
Application for plugging filed 5-18-51 19
Application for plugging approved 5-18-51 19
Plugging commenced 5-18-51 19
Plugging completed 5-18-51 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4275 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	248'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Bottom plug at 220' with 15 sacks of cement and the top plug set at 40' with 10 sacks of cement, this cemented to the top of surface.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Harry Gore 5-24-51
Address 400 Brown Building
Wichita, Kansas

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.
FLOYD W. HILD (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VENDOR SUPPLY & DEVELOPMENT COMPANY
(Signature) Floyd W. Hild
P. O. Box 201, Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May 1951
Chas Lawson
Notary Public.

My commission expires July 11, 1952

23-5004-s 8-50-10M
PLUGGING
FILE SEC 15 T 7 R 25W
BOOK PAGE 83 LINE 27

Company Harry Gore

15-065-00186-00-00

Sec. 15 T. 7 R. 25

Farm Moore

No. 1

Loc. NE NE NE

County Graham County, Kansas

Total Depth 4275'

Comm. 5-4-51

Comp. 5-18-51

Shot or Treated


Contractor Veeder Supply Company

Drilled with Rig - D.

Issued

No. of Days - 15

No. of Bitts -



Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Run 248' of 8-5/8" Csg. Cemented with 160 sacks cement.

Elevation

Production

Figures Indicate Bottom of Formation

Surface Soil	0	20	20	<u>Tops:</u>	
Sandy Clay	20	90	70	Heebner	- 3693
Sand Gravel	90	230	140	Lansing K.C.	- 3731
Shale	230	335	105	Base K.C.	- 3934
Blue Shale	335	460	125	Sandy Conglomerate	- 4162
Gray Shale	460	630	170	Cherty	- 4185
Shale Shells	630	1160	530	Arbuckle	- 4240
Sand Shale Shells	1160	1250	90		
Shale Shells	1250	1655	405		
Shale Shells Sand	1655	1800	145		
Red Bed Shells Sand	1800	2100	300		
Red Bed Shells	2100	2185	85		
Anhydrite	2185	2228	43		
Shale Shells Red Bed	2228	2505	277		
Shale Shells	2505	2700	195		
Lime Shale	2700	2835	135		
Lime	2835	2875	40		
Lime Shale	2875	3060	185		
Lime	3060	3260	200		
Lime Shale	3260	3445	185		
Lime	3445	3945	500		
Lime Shale	3945	4005	60		
Lime Shale Conglomerate	4005	4065	60		
Cherty Lime Shale	4065	4090	25		
Lime Shale	4090	4140	50		
Lime Shale Chert	4140	4200	60		
Conglomerate Cherty	4200	4243	43		
Arbuckle Lime	4243	4275	32		
Total Depth	4275'				

Plugged @ 220' with 15 sacks cement.

Plugged @ 40' with 10 sacks cement.

RECEIVED
REGISTRATION COMMISSION

MAY 24 1951

REGISTRATION DIVISION
Wichita, Kansas

5-24-51

PLUGGING
 FILE SEC 15 T 7 R 25
 BOOK PAGE 83 LINE 27