

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 065-22790 0000

LEASE NAME Fountain

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
3330308 Ft. from S Section L
4840 Ft. from E Section L

SEC. 10 TWP. 7S RGE. 23W (X) (W)

COUNTY Graham

Date Well Completed 3/3/98

Plugging Commenced 4:15AM3/3/98

Plugging Completed 8:00AM3/3/98

LEASE OPERATOR UNION VALLEY PETROLEUM CORPORATION

ADDRESS R.R. # 4, Box 120-Y Enid, OK 73701

PHONE# (405) 237-3959 OPERATORS LICENSE NO. 04941

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/2/98

by Richard Williams

(KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	211	8 5/8	211.38	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from _____ feet to _____ feet each
1st Plug @ 2115'w/25sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes with 48 Vis Mud
2nd Plug @ 1300'w/100sks 15sks In Rat Hole Plugs displaced with drilling mud.
3rd Plug @ 260'w/40sks Total 200sks 60/40Poz 6%Gel w/1#FS/sk By Allied Cementing
4th Plug @ 40'w/10sks Completed @ 8:00AM 3/3/98

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: UNION VALLEY PETROLEUM CORPORATION

STATE OF Oklahoma COUNTY OF Garfield, ss.

Paul Youngblood (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the statements; and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) _____

(Address) R.R. 4, Box 120-Y Enid OK 73701


SUBSCRIBED AND SWORN TO before me this 20th day of March, 19 98

Gayla S. Youngblood
Notary Public

My Commission Expires: 4/15/98

4/15/98

USE ONLY ONE SIDE OF EACH FORM



MAR 23 1998

Form Revised 6

3-23-98