

15-065-00648-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham

County. Sec. 8 Twp. 7 Rge. (E) 23 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Herndon Drilling Company

Lease Name Barrow Well No. 1

Office Address P. O. Drawer 489, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 7-10 19 60

Application for plugging filed 7-10 19 60

Application for plugging approved 7-10 19 60

Plugging commenced 7-10 19 60

Plugging completed 7-10 19 60

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Hill City, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3930 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 40 feet to 500 feet for each plug set.

Hole filled to 500 feet Rotary Mud
1st plug set @ 500 ft. and 20 sx. cement on plug.
2nd plug @ 300 ft. w/20 sx. cement on plug.
Top plug @ 40 ft. 10 sx. cement.
Cement was mixed and pumped thru drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Globe Cementing Company, Hill City, Kansas 7-28-60
Address

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
Tom Elliott

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom Elliott
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 1960

My commission expires June 19, 1961
Johnnie Alene Frese Notary Public.



15-065-00048-00-00

re
WELL LOG

Well: **BARROW NO. 1**
Location: **NE NE SW Sec. 8-78-23W,**
Owner: **Graham County, Kansas**
Herndon Drilling Company

Spudding date: **6-29-60**
Date casing set: **6-29-60**
Date rotary completed: **7-10-60**
Date cable completed:

FROM	TO	FORMATION	REMARKS
0	820	Surface Hole	Ran 10 joints 8-5/8" casing (308.81') Pipe set @ 320'. Cemented w/150 ex. cement. Cement circulated.
820	1530	Shale & Sand	
1530	1558	Shale	
1558	1625	Shale & Shells	
1625	1950	Shale, Shells & Sand	
1950	2015	Lime	
2015	2110	Shale & Shells	
2110	2150	Anhydrite	
2150	2815	Shale & Shells	
2815	2950	Shale, Shells & Lime	
2950	3650	Lime & Shale	
3650	3930	Lime	
	3930	Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1960

CONSERVATION DIVISION
Topeka, Kansas

7-28-60

Subscribed and sworn to before me this 15th
day of July, 19 60

I certify the above and foregoing to be a true and exact copy
of the original driller's log on the BARROW NO. 1

HERNDON DRILLING COMPANY

Johanna Alene Fiese
Notary Public
My commission expires:

By: *C. T. Moore*
Title: **C. T. Moore, Asst. Secty.**

June 19, 1961