

15-065-00723-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 11 Twp. 7S Rge. 23W (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner J.A. Terteling & Sons
Lease Name Hale Well No. 1
Office Address Frank Wood Bldg., Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 17 19 55
Application for plugging filed Dec. 17 19 55
Application for plugging approved Dec. 17 (orally) 19 55
Plugging commenced Dec. 17 19 55
Plugging completed Dec. 17 19 55
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4058 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	209'	8 5/8"	209	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole from total depth to 200' with mud. Set plug at 200' with 15 sacks of cement on top of plug. Filled with heavy mud to 40' with plug set there and 10 sacks of cement on top of plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Co.
Address Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. C.H. Slinkard (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.H. Slinkard
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of January, 1956

My commission expires 1-20-58

Mary E Van Pelt
Notary Public.

PLUGGING
FILE SEC 11 T 7 R 23W
BOOK PAGE 26 LINE 8

RECEIVED
STATE CORPORATION COMMISSION

1-6-56

Driller's Log

Company: J. A. Terteling & Sons
Farm: Hale #1

NE NE NW Section 11-7S-23W
Graham County, Kansas

Commenced: December 5, 1955

Completed: December 17, 1955

Elevation: 2388 K B

0 - 95	Clay	2620 -2745	Shale & Lime
95 - 115	Sand & Clay	2745 -3400	Lime & Shale
115 -1000	Shale	3400 -3470	Lime
1000 -1105	Sand & Shale	3470 -3635	Lime & Shale
1105 -1310	Shale	3635 -3850	Lime
1310 -1695	Shale & Shells	3850 -3870	Shale & Lime
1695 -1800	Sand	3870 -3925	Lime & Shale
1800 -2035	Shale & Shells	3925 -3980	Lime
2035 -2062	Anhydrite	3980 -4035	Conglomerate
2062 -2620	Shale & Shells	4035 -4058	Lime, Arbuckle
		4058	Total Depth

Set 209 feet 8 5/8" surface pipe. Cemented with 150 sacks cement and 3 sacks calcium chloride.

Tops:

Anhydrite	2035
Lansing	3925
Conglomerate	3980
Arbuckle	4035

Drill Stem Tests: #1 3636-3667 Open 1 hr. Shut in 20 min.
Recovered 50 ft. mud BHP

#2 3670-3705 Open 1 hr. Shut in 30 min.
Recovered 124 ft. salt water and mud. BHP 1235#.

#3 3714-3730 Open 1 hr. Shut in 30 min.
Recovered 1065 ft. salt water. BHP 1070#.

#4 3754-3790 Open 1 half hr. Shut in 30 min.
Recovered 30 ft. mud.

#5 3795-3850 Open 35 min. Shut in 30 min.
Recovered 20 ft. mud.

Dry, Plugged, and Abandoned.

Affidavit:

State of Kansas)
County of Barton) SS.


I, C.H. Slinkard of J.A. Terteling & Sons, being first duly sworn on oath state: I have knowledge of the facts, statements, and matters herein contained and the same are true and correct.

Signed C. H. Slinkard

Subscribed and sworn to before me the 5 day of January 1956

Comm. Exp. 1-20-58

Mary E Van Belt
Notary Public



DIVISION

1-6-56