

15-065-20401-00-00

JAN 11 1971

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202


WELL PLUGGING RECORD

DEPT.

Graham County. Sec. 10 Twp. 7S Rge. 23 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines 50'S of NE SE NE
Lease Owner Clinton Oil Company
Lease Name Hale Well No. 1-V
Office Address 217 N. Water, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 21 19 70
Application for plugging filed December 21 19 70
Application for plugging approved December 21 19 70
Plugging commenced December 21 19 70
Plugging completed December 21 19 70
Reason for abandonment of well or producing formation No Productible Zone

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	357	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Gunned up pits forming heavy mud - Filled hole to 1250 feet with heavy mud - Pushed plug to 1250 feet and cemented with 70 sacks cement - Filled hole to 365 feet with heavy mud - Pushed plug to 365 feet and cemented with 20 sacks cement - Filled hole with heavy mud - Pushed plug and hulls to 40 feet - Cemented with 10 sacks cement to base of well cellar

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1971
CONSERVATION DIVISION
Wichita, Kansas

11-15-71

Name of Plugging Contractor Garvey Drilling Company (If additional description is necessary, use BACK of this sheet)
Address Box 1164, Great Bend, Kansas 67530 1-15-71

STATE OF Kansas, COUNTY OF Barton, ss. Ben Unruh

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E Unruh
Box 1164, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1971

My commission expires July 8, 1974
Notary Public.

WELL LOG

15-009-20401-00-00

COMPANY Clinton Oil Company

FARM F. S. Hale NO. 1-V

TOTAL DEPTH 3840'

COMM. 12-14-70 COMP. 12-21-70


CONTRACTOR Garvey Drilling Company

SEC. 10 T. 7S R. 23W

LOC. NE SE NE

COUNTY Graham, Kansas

CASING
8 5/8" @ 358' w/200sx



ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 175' Sand & Shale
- 358' Shale
- 1040' Sand
- 1310' Shale & Shells
- 1346' Shale
- 1780' Sand
- 1900' Shale
- 2065' Anhydrite
- 2180' Shale & Shells
- 2780' Shale
- 3065' Shale & Lime
- 3635' Lime & Shale
- 3790' Lime
- 3840' Lime
- 3840' RTD

15-71
RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1971
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
JAN 18 1971
PRODUCTION DEPT.

State of Kansas }
County of Barton } ss

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the F. S. Hale No. 1-V well.

Subscribed and sworn to before me this 12th day of January 1971

My Commission Expires: July 8, 1974

Charlene Marker

Terence A. Thomas

NOTARY PUBLIC