


15-065-02620-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 8 Twp. 7S Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines C/SW/SE4
Lease Owner Glickman Oil Company
Lease Name Barrow Well No. 1
Office Address 702 S. St. Francis, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 9, 1962
Application for plugging filed August 9, 1962
Application for plugging approved August 9, 1962
Plugging commenced August 9, 1962
Plugging completed August 9, 1962
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hayes, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3870 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it to the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 550' w/20 sxs cement-1/4 sx hulls.
Plug at 180 with same. Plug at 35 with 10 sxs cement-1/2 hulls.

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1962
CONSERVATION DIVISION
Wichita, Kansas

8-16-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glickman Oil Company
Address P. O. Box 3104, Washington Street Station, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Milton Glickman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Milton Glickman
Milton Glickman Partner
P. O. Box 3104, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1962

My commission expires November 19, 1963
Lorella Schauf Notary Public.



15-065-02620-00-00

GLICKMAN OIL COMPANY

P. O. Box 3108 + 3104

Wichita, Kansas

DRILLERS WELL LOG

Company: Glickman Oil Company

Location: C/SW/SE/4

Farm: Barrow

Well No. 1

Sec. 8-7S-23W

Graham County, Kansas

Commenced: August 1, 1962

Elevation: 2394 K. B.

Completed: August 9, 1962

Total Depth: 3870'

Casing: 8-5/8" @ 195' w/150 sxs.

Production: D & A

Geologist - Al Stude

Figures Indicate Bottom of Formations

194	Soil Sand & Shale	Tops:	
820	Shale	Anhydrite	2080
1665	Shale & Shells	Toronto	3651
1840	Sand w/Shale Streaks	Lansing	3664
2080	Red Bed & Shale		
2116	Anhydrite		
2130	Red Bed		
2395	Shale		
2830	Shale & Lime		
3575	Lime & Shale		
3650	Lime		
3710	Lime & Shale		
3840	Lime		
3870	Lime & Shale		
3870	RTD		

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1962

CONSERVATION DIVISION
Wichita, Kansas

8-16-62

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Barrow #1

Milton Glickman Partner

Subscribed and sworn to before me this 14th day of August, 1962.

Lorella Schauf Notary Public

My Commission Expires: November 19, 1963