

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County, Sec. 28 Twp. 7 Rge. (E) 25(W)

Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Cities Service Oil Co.
Lease Name Maupin Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry-hole
Date well completed 12/13/55 19
Application for plugging filed 12/13/55 19
Application for plugging approved 12/15/55 19
Plugging commenced 12/13/55 19
Plugging completed 12/14/55 19
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	239'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill with heavy mud to 230', set wooden plug with 1/2 sack hulls. Ran 15 sx cement, fill with heavy mud to 40'; set wooden plug with 1/2 sack hulls, fill to surface with ten sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Co.
Address Tulsa, Oklahoma


STATE OF KANSAS, COUNTY OF BARTON, ss.
Roy J. Turner (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Roy J. Turner
Box 553, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of December, 1955

W. J. Smith
Notary Public.

My commission expires March 17, 1959



DEC 27, 1955

WELL RECORD

Company Cities Service Oil Co. et al. Well No. 1 Farm Neupin
 Location 330' South and 330' West of N/4 Corner Sec. 28 T. 7 R. 25W
 Elevation 2541 (2539 Cr.) County Graham State Kansas
 Drlg. Comm. December 2, 1955 Contractor Barbour Drilling Company
 Drlg. Comp. December 13, 1955 Acid None
 T. D. 3890' Initial Prod. Dry Hole - P. & A. December 13, 1955

CASING RECORD:

8-5/8" @ 239' cem. 225 sx cement

FORMATION RECORD:

shale	0-140
sand	195
shale & shells	880
shale, shells & sand	1330
shale & shells	1865
sand	1965
red bed & shells	2156
anhydrite	2186
red bed, shale & shells	2365
shale & shells	2680
lime & shale	2895
shale & lime	3005
lime & shale	3150
shale & lime	3225
sand, shale & lime streaks	3350
lime & shale	3670
lime	3812
lime & shale	3865
lime	3890 T. D.

Topoka	3444'
Heebner	3642'
Dodge	3664'
Lansing	3682'
Base Kansas City	3883'
Total Depth	3890'

D. S. T. 3704-16, open 30 mins., rec.
 20' mud; B. H. P. 1200#/30 mins.
 D. S. T. 3715-30, open 30 mins., rec.
 20' mud; B. H. P. 1160#/30 mins.
 D. S. T. 3749-60, open 30 mins., rec.
 24' mud; B. H. P. 1210#/30 mins.
 D. S. T. 3791-3812, open 30 mins., rec.
 57' mud; B. H. P. 115#/30 mins.
 D. S. T. 3834-65, open 30 mins., rec.
 15' mud; B. H. P. 750#/30 mins.

SLOPE TESTS (SYFO):

500'	1°
1000'	1°
1500'	1°
2000'	1°
2500'	2°
3000'	0°
3500'	0°

7-7/8" rotary hole.

DEC 27, 1955

PLUGGING

FILE SEC 28 T. 7 R. 25W
 BOOK PAGE 24 LINE 23

