

RECEIVED
STATE CORPORATION COMMISSION
FOLIO P-4
Rev. 12-15-80
JUL - 7 1982
JUL 7 1982
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 28 TWP. 7S RGE. 25 NE/W
Location as in quarters or footage from lines:
990' FSL - 1650' FEL of N/4 Corner

Locate Well
correctly on above
Section Platt.

Lease Owner Cities Service Company
Lease Name Blazier LKC Unit Well No. 302
Office Address 209 E. William, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed December 10, 1955
Application for plugging filed March 22, 1982
Plugging commenced June 9, 1982
Plugging completed June 9, 1982
Reason for abandonment of well or producing formation Bad casing in the well.

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Lansing-KC Depth to top 3776' bottom 3786' T.D. 3875'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	238'	-0-
				5 1/2"	3875'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 1275' of 2" tubing. Cement with 190 sacks 50-50 Pozmix plus 6% gel plus 3% CaCl plus 3 sacks hulls. Cement circulated. Pulled 2" tubing. Plug and abandon completed June 9, 1982.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles E. Forrester (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles E. Forrester
Charles E. Forrester

(Address) 209 E. William, Wichita, KS 67202

2 day of July 19 82

JACQUELINE PIERCE
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires
2-27-85

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1982
CONSERVATION DIVISION
Wichita, Kansas

SWORN TO before me this

Jacqueline Pierce
Jacqueline Pierce - Notary Public.

My Commission expires: 2-27-85