

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
67202 TYPE OR PRINT

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22664-00-01
LEASE NAME PARKER B Wichita, KS

WELL NUMBER 1

NOTICE: Fill out **completely** 4950 Ft. from S Section Line
and return to Cons. Div. 330 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 6 TWP. 7S RGE. 23W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY GRAHAM
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 3/8/92
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 6/7/02
Plugging Completed 6/7/02

The plugging proposal was approved on 6/7/02 (date)
by PAT STAAB w/KCC Hays, KS. (KCC District Agent's Name).
Is ACO-1 filed? YES If not, is well log attached? NO
Producing Formation LKC Depth to Top 3770 Bottom 3895OA TD 3960' PBTD3916

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	288	8 5/8	288	0
		production	3857	5 1/2	3857	

6-19-2002
RECEIVED
JUN 19 2002
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Down 8 5/8" pumped 15sxs 60/40 poz 10%gel, max press#300 ISIP200#. Down 5 1/2" csg pumped 305 sxs 60-40poz, 10% gel, 700#hulls, max press 700#, ISIP600#. Well P/A. Witnessed and approved by Pat Staab w/ KCC

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 10 th day of June, 2002

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



OK