

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-20,730-0000

LEASE NAME WHITE

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 5 TWP. 7S RGE. 23 (W)

COUNTY Graham

Date Well Completed 1-18-75

Plugging Commenced 6-18-86

Plugging Completed 6-18-86

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# 918) 494-0000 OPERATORS' LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays

Is ACO-1 filed? on old form If not, is well log attached? ---

Producing Formation Lansing Depth to Top 3908 Bottom 3912 T.D. 3965

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil	3908	12	8-5/8	292	-0-
				4-1/2	3964	605

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Bottom hole plug from TD to 3858' w/sand + 4 SXS cement. Pumped 250 SXS 65% common, 35% poz, 10% gel + 6 SXS hulls from 2500' to SURF. Pumped 250' SXS thrifty-mix w/6 SXS hulls down annulus.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg
(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 86

Carol Sue Brumbaugh
Notary Public

My Commission Expires: 2/11/89

RECEIVED
STATE CORPORATION COMMISSION

Form CP-4
Revised 08-84

JUL - 9 1986 7-9-86

CONSERVATION DIVISION

15-065-20730-00-00

DRILLERS LOG

WHITE #1


CASING RECORD:	OPERATOR:	Patrick Petroleum Corp.	DESCRIPTION:
292' w/ 8-5/8"	CONTRACTOR:	John O. Farmer, Inc.	NW NE NW
Cemented w/ 225 sx.	COMMENCED:	January 9, 1975	Sec. 5-7S-23W
3964' w/ 4 1/2"	COMPLETED:	January 18, 1975	Graham County,
Cemented w/ 150 sx.			Kansas
TOTAL DEPTH:			
3965'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	295	765	
Shale & Sand	765	1355	
Shale & Shells	1355	1630	
Shale	1630	1735	
Sand	1735	1930	
Red Bed	1930	2179	
Anhydrite	2179	2217	
Shale & Shells	2217	2495	
Shale & Lime	2495	2875	
Shale	2875	3025	
Shale & Lime	3025	3595	
Lime & Shale	3595	3740	
Lime	3740	3846	
Lime & Shale	3846	3900	
Lime	3900	3940	
Lime & Shale	3940	3965	
Total Depth	3965		

I certify that this is a true and correct copy of the above log to the best of my knowledge.

JOHN O. FARMER, INC.

By: John O. Farmer
John O. Farmer, President & Contractor



Subscribed and sworn to before me this 27th day of January, 1975.

My Commission Expires:
February 15, 1975

Helen Carlson
Helen Carlson, Notary Public