


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 30 Twp. 7S Rge. (E) 25(W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Imperial Oil Company
Lease Name Dawes Well No. 1
Office Address 780 Fourth National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 5 19 67
Application for plugging filed September 5 19 67
Application for plugging approved September 5 19 67
Plugging commenced September 5 19 67
Plugging completed September 5 19 67
Reason for abandonment of well or producing formation No commercial quantities of oil were found.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3942 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface casing at	207 ft.	8 5/8"			Not pulled.
	with 165 sacks cement					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3942 feet to _____ feet for each plug set.

Set first plug at 2000 ft. with 100 sacks cement.
Set second plug at 210 ft. with 20 sacks cement.
Set third plug at 40 ft. with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil Company
Address 780 Fourth National Bldg., 110 No. Market, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Charley V. Shank (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

IMPERIAL OIL COMPANY
(Signature) Charley V. Shank
Charley V. Shank
780 Fourth National Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of September, 19 67

My commission expires March 3, 1970

Mary J. Brown
Mary J. Brown Notary Public.

Received
9-19-67

DRILLER'S LOG

Imperial Oil Company
780 Fourth National Bldg.
Wichita, Kansas

No. 1 Dawes
C SE NE Sec. 30-7S-25W
Graham County, Kansas

Total Depth: 3942 ft.

Elevation: 2473 K.B.

Commenced: 8-29-67

Completed: 9-5-67
Dry Hole

Contractor: Imperial Oil Company - Rig #2

Casing Record: Set 8 5/8 inch surface casing at 207' with 165 sacks of cement.

Figures indicate bottom of formations:

	<u>Sample Tops:</u>	
207' Sand-shale	Anhydrite	2160 (+ 313)
1785' Shale-shells	Base Anhydrite	2195 (+ 278)
1945' Dakota Sand	Heebner	3679 (-1206)
2160' Shale-shells	Lansing	3717 (-1244)
2195' Anhydrite	Base Kansas City	3934 (-1461)
2605' Shale-shells	Rotary Total Depth	3942 (-1467)
2815' Shale+lime		
2935' Lime-shale		
3058' Shale-lime		
3240' Lime-shale		
3530' Shale-lime		
3643' Lime		
3785' Lime-shale		
3942' Lime		
<u>3942' Rotary Total Depth</u>		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Charley V. Shank
Charley V. Shank

Subscribed and sworn to before me this 19th day of September, 1967.

Mary J. Brown
Mary J. Brown, Notary Puylic

My Commission Expires:
March 3, 1970

Received
9-19-67
HEB
7/6/2005