

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 36 Twp. 7S Rge. (E) 25(W)

Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Chief Drilling Co., Inc.
Lease Name H. MOORE Well No. 2
Office Address Box 797 - Gt. Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/7 19 67
Application for plugging filed 3/7 19 67
Application for plugging approved 3/7 19 67
Plugging commenced 3/7 19 67
Plugging completed 3/7 19 67
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3985 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	210	8-5/8	210	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 540'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 210'
Mixed 20 sacks cement through drill pipe
Hulls & wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
MAR 9 1967
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Gt. Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover
CHIEF DRILLING CO., INC.
Box 797 - Gt. Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 67
Carmen R. Cook
Carmen R. Cook, Notary Public.

My commission expires Dec. 12, 1970

WELL LOG

Chief Drilling Co., Inc.
 Box 797
 Great Bend, Kansas 67530

H. MOORE #2
 C SE NE Sec. 36-7S-25W
 Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 3-1-67
 Completed: 3-7-67

Casing Record: 8-5/8" @ 210' w/175 sacks Sunset Cement.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Shale	0	217	2496 Gr.
Shale	217	525	2498 D.F.
Shale & Sand	525	650	2501 K.B.
Shale	650	1115	
Shale & Shells	1115	1700	
Shale	1700	2196	
Anhydrite	2196	2231	
Shale & Lime	2231	3550	
Lime	3550	3752	
Lime & Shale	3752	3788	
Lime	3788	3985	
Total Depth			

			<u>FORMATION TOPS</u>
Anhydrite	2196	+ 305	
Heebner	3752	-1251	
Toronto	3778	-1277	
Lansing	3788	-1287	
Total Depth	3985	-1484	

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 9 1967
 MAR 9 1967
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SE NE Section 36-7S-25W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
 V. Richard Hoover, President

Subscribed and sworn to before me this 8th day of March, 1967.

Carmen R. Cook
 Carmen R. Cook, Notary Public

My commission expires: Dec. 12, 1970.