


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 36 Twp. 7S Rge. (E) 25 (W)
Location as "NE/CNW%SW%" or footage from lines NW NW
Lease Owner Chief Drilling Co., Inc.
Lease Name MOORE "B" Well No. 2
Office Address Box 797 - Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/5 1968
Application for plugging filed 2/5 1968
Application for plugging approved 2/5 1968
Plugging commenced 2/5 1968
Plugging completed 2/5 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3975 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	212	8-5/8"	212	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 1220'
Mixed 70 sacks cement through drill pipe
Wooden plug set @ 240'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe


RECEIVED
STATE CORPORATION COMMISSION
FEB 7 - 1968
CONSERVATION DIVISION
Wichita, Kansas
Feb 7, 1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Thomas G. Wesselowski (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas G. Wesselowski
Box 797 - Gt. Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 6th day of February, 1968



Carmen R. Cook
Carmen R. Cook, Notary Public.

WELL LOG

Chief Drilling Co., Inc.
 Box 797
 Great Bend, Kansas 67530

MOORE "B" #2
 NW NW Sec. 36-7S-25W
 Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 1-29-68
 Completed: 2-5-68

Casing Record: 8-5/8" @ 212' with 160 sacks 60/40 Pozmix, 2% Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand & Gravel	0	190	2464 Gr.
Shale & Sand Streaks	190	212	2466 D.F.
Shale	212	1100	2469 K.B.
Shale & Sand	1100	1205	
Shale, Shells & Sand Streaks	1205	1700	<u>FORMATION TOPS</u>
Shale & Shells	1700	1750	Anhydrite 2172 + 297
Sand	1750	1940	Heebner 3719 -1250
Shale & Shells	1940	2172	Toronto 3743 -1274
Anhydrite	2172	2207	Lansing 3759 -1290
Shale & Shells	2207	2460	Base Kansas City 3971 -1502
Shale & Lime Streaks	2460	2715	Total Depth 3975 -1506
Lime & Shale	2715	3660	
Lime	3660	3755	
Lime & Shale	3755	3975	
Total Depth	3975		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW NW Section 36-7S-25W, Graham County, Kansas, to the best of my knowledge and belief.

RECEIVED
 STATE CORPORATION COMMISSION
 Feb 7, 1968 FEB 7 - 1968
 CONSERVATION DIVISION
 Wichita, Kansas

CHIEF DRILLING CO., INC.

Thomas Wesselowski
 Thomas Wesselowski, Geologist

Subscribed and sworn to before me this 6th day of February, 1968.

Carmen R. Cook
 Carmen R. Cook, Notary Public

Commission expires: Dec. 12, 1970.

