

RECEIVED
JAN 25 2006
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 185 - 22340 - DD - D1 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 1-16-1986.

Well Operator: ZU LLC KCC License #: 32699
(Owner / Company Name) (Operator's)

Address: 108 West 34th City: HAYS

State: KANSAS Zip Code: 67601 Contact Phone: (785) 625 - 6588

Lease: ZENITH WATERFLOOD Well #: 35 Sec. 1 Twp. 24 S. R. 11 East West

C - S/2 Spot Location / QQQQ County: STAFFORD

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2640 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # E-12893 Other: _____

Conductor Casing Size: 8.5 Set at: 212 Cemented with: 150 Sacks

Surface Casing Size: 5.5 Set at: 3817 Cemented with: 175 Sacks

Production Casing Size: 3.5 Set at: 3757 Cemented with: UNKNOWN Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFED @ 3703-3717 W/36 HOLES

Elevation: 1798 (G.L. / K.B.) T.D.: 3818 P.B.T.D.: _____ Anhydrite Depth: 550'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): RUN IN WITH TUBING TO 3600 FEET, SPOT 40 SACKS OF 60/40 W/6% GEL, ONE BAG OF CALCIUM AND 300# COTTONSEED HULLS ON BOTTOM. WAIT ONE HOUR, PRESSURE UP CASING TO 200 PSI, IF IT HOLDS THEN PERF @ 550' ONE FOOT 4 SPF, THEN TRY TO CIRCULATE CEMENT TO SURFACE ON BACKSIDE AND FILL CASING WITH CEMENT. IF IT DOES NOT HOLD THEN SPOT CEMENT @ 690', WAIT ONE HOUR AND FINISH PLUGGING.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: GREG WHITEHAIR,

ZU LLC Phone: (785) 432 - 0789

Address: 108 West 34th, Hays, Kansas 67601 City / State: HAYS, KANSAS 67601

Plugging Contractor: KLIMA WELL SERVICE - Allied KCC License #: 7023
(Company Name) (Contractor's)

Address: PO BOX 386, CLAFLIN, KANSAS 67525 Phone: (620) 587 - 3333

Proposed Date and Hour of Plugging (if known?): WEDNESDAY JANUARY 25TH, 9:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/23/2006 Authorized Operator / Agent: ZU LLC By Greg Whitehair
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ZU, LLC
108 West 34th
Hays, KS 67601

January 26, 2006

Re: ZENITH WATERFLOOD UNIT #35
API 15-185-22340-00-01
S2 1-24S-11W, 1320 FSL 2640 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor