

RECEIVED

JAN 24 2006

Form CP-4

December 2003

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Fill in Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Lario Oil & Gas Company

Address: 301 S. Market St.; Wichita, KS 67202

Phone: (316) 265-5611 Operator License #: 5214

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/02/2005 (Date)

by: Jay Pfeifer - Hays (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Simpson Sd. Depth to Top: 3450 Bottom: 3454 T.D. Arbuckle Depth to Top: 3455 Bottom: 3461 T.D. 3461

API Number: 15-051-05046-00-00

Lease Name: Bemis "F"

Well Number: 5

Spot Location (QQQQ): - SE - SW - SE 330 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 28 Twp. 11 S. R. 17 East West

County: Ellis

Date Well Completed: 10/14/1946

Plugging Commenced: 12/07/2005

Plugging Completed: 12/07/2005

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes 8-5/8" and 5-1/2" with depths 1146' and 3455'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged with 320 sks 60/40 (Poz)+10% Gel + 500# Hulls as follows:

Perfs Sqz holes @ 570', 1180' & 1750'. Run tbg (oe) to 2350'. Pump 220 sks + hulls,

Circ between surf csg / prod csg / tbg. LD tbg. Pump 80 sks down 5-1/2", circ. SI csg valve.

Pump additional 20 sks to 300 psi. Note: 5-1/2" TST Packer stuck @ 2400'.

Name of Plugging Contractor: Allied Cementing Co. License #:

Address: P.O. Box 31; Russell, KS 67665

Name of Party Responsible for Plugging Fees: Lario Oil & Gas Co.

State of Kansas County, Sedgwick, ss.

Jay G. Schweikert, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jay Schweikert

(Address) 301 S. Market St.; Wichita, KS 67202

KATHY L. FORD Notary Public - State of Kansas My Appt. Expires 10-22-06 SUBSCRIBED and SWORN TO before me this 23 rd day of January, 20 06 My Commission Expires: 10-22-06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Allied Cementing Co., Inc
P.O. Box 31

Russell, KS 67665

* * * * *
* I N V O I C E *
* * * * *

Invoice Number: 099789

Invoice Date: 12/09/05

RECEIVED
JAN 24 2006
KCC WICHITA

Sold Lario Oil & Gas Company
To: P. O. Box 784
Hays, KS
67601

Cust I.D.....: Lario AFE #04-130
P.O. Number...: Bemis F #5 (PA'd)
P.O. Date.....: 12/09/05

Due Date.: 01/08/06
Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	190.00	SKS	8.7000	1653.00	T
Proxmix	130.00	SKS	4.7000	611.00	T
Fulls	5.00	SKS	21.0000	105.00	T
Del	28.00	SKS	14.0000	392.00	T
Handling & Mileage	1.00	PER	1520.6400	1520.64	T
Plug	1.00	JOB	785.0000	785.00	T
Mileage pmp trk	36.00	MILE	5.0000	180.00	T

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$524.66
ONLY if paid within 30 days from Invoice Date

Subtotal: 5246.64
Tax.....: 278.07
Payments: 0.00
Total....: 5524.71

Jim Billoggy
12-13-05

all
SC OK to Pay

Acct.	Expl.	File				
DEC 14 2005						
CA	<i>all</i>					
KG						
HY	JS	KF	GV	SF	DM	
PV	<i>ye</i>					
OD						

