

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Mai Oil Operations, Inc.

Address: P.O. Box 33, Russell, Ks. 67665

Phone: (785) 483-2169 Operator License #: 5259

Type of Well: D&A Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. (repeated three times)

API Number: 15-009-24882-0000

Lease Name: O'Leary

Well Number: 6

Spot Location (QQQQ): NE - SW - NE -

1650 Feet from North / South Section Line

1670 Feet from East / West Section Line

Sec. 8 Twp. 16 S. R. 11 East West

County: Barton

Date Well Completed: 11-22-05

Plugging Commenced: 11-22-05

Plugging Completed: 11-22-05

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 0, 389', 8 5/8", Cemented.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Run drill pipe to 3276', spot 25 sks, pull to 690', spot 25 sks, pull to 440', spot 75 sks, pull to 40', spot 10 sks, pump 15 sks

Rat Hole. All cement 60-40 POZ, 6% Gel, 1/4# PS Floccel

Name of Plugging Contractor: Allied Cementing - Murfin Drilling License #: 30606

Address: 24 S. Lincoln, Russell, Ks. 67665

Name of Party Responsible for Plugging Fees: Mai Oil Operations, Inc.

State of Kansas County, Russell, ss.

Allen Bangert (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Allen Bangert

(Address) P.O. Box 33, Russell, Ks. 67665

SUBSCRIBED and SWORN TO before me this 23 day of Jan, 2006



Sherril Underwood Notary Public My Commission Expires: 10-30-08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED JAN 25 2006 KCC WICHITA

KCC BEM 1-25-06 RBDMS CP 2/3