

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD JAN 26 2006  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

KCC WICHITA

Lease Operator: Vincent Oil Corporation  
Address: 125 N. Market, Suite 1075 Wichita, KS 67202  
Phone: (316) 262-3573 Operator License #: 5004  
Type of Well: ENHR Docket #: E-26863.2  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 1-4-06 (Date)  
by: Jay Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L.K.C. Depth to Top: 3316 Bottom: 3402 T.D. 3471  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-009-22827-0002  
Lease Name: Evers  
Well Number: A-2  
Spot Location (QQQQ): NE - SE - NW - NW  
4480 Feet from  North /  South Section Line  
4210 Feet from  East /  West Section Line  
Sec. 24 Twp. 19 S. R. 14  East  West  
County: ~~Barton~~ Barton  
Date Well Completed: ~~7-30-52~~ 6-15-1998  
Plugging Commenced: 1-04-06  
Plugging Completed: 1-06-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	oil	3316	3404	8 5/8 in.	791 ft.	0 ft.
				5 1/2 14#	3467 ft.	2205 ft.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole sand at 3265', bailed 5 sacks of cement, ripped at 2440' and 2205'. Pulled to 1650', pumped 120 sacks and 3# hulls, pulled to 790', pumped 40 sacks, 100# of hulls, pulled to 250' and circulated with 65 sacks

Name of Plugging Contractor: Quality Well Service License #: 31925  
Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation  
State of Kansas County, Sedgwick, ss.

Richard A. Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

*Richard A. Hiebsch*


(Address) 125 N. Market, Suite 1075 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 25 day of January

20 06

Yolanda Eubanks  
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Benn*

# ALLIED CEMENTING CO., INC. 24106

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Great Bend

DATE <u>1-6-06</u>	SEC. <u>24</u>	TWP. <u>19</u>	RANGE <u>14w</u>	CALLED OUT <u>8 AM</u>	ON LOCATION <u>11 AM</u>	JOB START <u>12 PM</u>	JOB FINISH <u>2 PM</u>
LEASE <u>Eve's</u>		WELL # <u>A 2</u>	LOCATION <u>96 Hwy + Fuzzy Brewer Corner</u>		COUNTY <u>Barton</u>	STATE <u>K.S.</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<u>2 E 3/4</u>				

CONTRACTOR Quality Well Ser

TYPE OF JOB old hole plug

HOLE SIZE \_\_\_\_\_ T.D. 3467

CASING SIZE 5 1/2 DEPTH 1650

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT

AMOUNT ORDERED 230.60 / 40 108 gal

400# Hull

COMMON	<u>138 gal</u>	@	<u>8.70</u>	<u>1200.60</u>
POZMIX	<u>92 gal</u>	@	<u>4.70</u>	<u>432.40</u>
GEL	<u>20 gal</u>	@	<u>14.00</u>	<u>280.00</u>
CHLORIDE		@		
ASC		@		
<u>Hulls 400#</u>		@	<u>2.100</u>	<u>84.00</u>

**RECEIVED**

**JAN 26 2006**

**KCC WICHITA**

HANDLING	<u>254 gal</u>	@	<u>1.60</u>	<u>406.40</u>
MILEAGE	<u>254.40</u>	@	<u>2.11</u>	<u>180.00</u>
<b>TOTAL</b>				<u>2583.40</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Mike M.

# 120 HELPER Robert B.

BULK TRUCK

# 341 DRIVER Terry L.

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

Mix 120 gal with 300# Hull to 1650 ft

Mix 40 gal with 100# Hull at 790 ft

Circulate Cement to surface from 250 ft

**SERVICE**

DEPTH OF JOB 1650 ft