

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-01014-00-01  
Spot: SENWSW Sec/Twnshp/Rge: 13-27S-10W  
1692 feet from S Section Line, 4376 feet from E Section Line  
Lease Name: MILBURN Well #: 1  
County: KINGMAN Total Vertical Depth: 4300 feet

Operator License No.: 31644  
Op Name: DELAWARE ENERGY CORPORATION  
Address: 8105 N MAYFIELD RD  
BUHLER, KS 67522

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4300	1550	
SURF	8.625	273		

#139<sup>75</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/04/2005 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/04/2005 12:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 5 sacks of cement on top of sand. Shot and pulled casing to 1500' and spotted 35 sacks of cement. Pulled to 1100' and spotted 35 sacks of cement. Pulled to 350' and circulated to surface with 100 sacks of cement.

60/40 posmix with 4% gel

Copeland Cementing #25817

Perfs:

RECEIVED  
KCC DISTRICT #2  
JAN 11 2006  
WICHITA, KS

RECEIVED  
JAN 26 2006  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)

INVOICED

DATE

1-26-06

INV NO

2006061015