

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-14328-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 3-20S-11W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: PANNING Well #: 7  
County: BARTON Total Vertical Depth: 3303 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3301	0	75 SX CMT
SURF	10.75	141	0	150 SX CMT

# 107<sup>35</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/24/2006 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-7461

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 10% gel - 1000# hulls.  
Log Tech perfed at 1325' and 500'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/24/2006 12:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2000'.  
Allied rigged to tubing and pumped 125 sxs 60/40 pozmix with 300# hulls mixed in.  
Pulled tubing to 1350' - pumped 100 sxs cement with 300# hulls mixed in.  
Pulled tubing to 500' - pumped 75 sxs cement with 400# hulls mixed in to circulate cement to surface.  
Pulled tubing - tied onto 7" casing with a swedge - pumped 20 sxs cement.  
Max. P.S.I. 550#. S.I.P. 300#.  
Dug out backside - was full of cement.

Perfs:

Top	Bot	Thru	Comments
3301	3303	OH	

Remarks: ALLIED CEMENTING COMPANY-TICKET #24720.

Plugged through: TBG

RECEIVED  
JAN 26 2006  
KCC WICHITA

District: 04

Signed: [Signature]  
(TECHNICIAN)

INVOICED

DATE 1-26-06  
REF NO 2006061013

Form CP-2/3

JAN 25 2006

BERGMAN OIL COMPANY

#7

PANNING

3-20-11W  
SW NW SE

Contr.

BARTON

County

E 1765

Comm.

Comp. 5-1-53

IP

25 BOPD

Tops	Depth	Datum
KC	3042	-1277
ARB	3299	-1534
TD	3303	-1538

Casing  
 8" 160  
 5" 3301

CHASE-SILICA

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

MAICED

Oil No. \_\_\_\_\_  
Well No. \_\_\_\_\_