

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22074-00-00
Spot: NESWNW Sec/Twnshp/Rge: 13-15S-19W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: GERSTNER Well #: 1
County: ELLIS Total Vertical Depth: 3750 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3694	0	w/525 sxs cmt
SURF	8.625	292	0	w/180 sxs cmt

Well Type: SWD UIC Docket No: D20168.0 Date/Time to Plug: 01/23/2006 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Tied onto the annulus - instant 800#.
Swaged onto 5 1/2" - mixed and pumped 275 sxs cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.


Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

RECEIVED
JAN 26 2006
KCC WICHITA

District: 04

Signed


(TECHNICIAN)

JAN 24 2006

ROY V ONFELDT
 524 ST JOHN
 RUSSELL, KS 67665
 #1 GERSHNER 13-15-19W
 NE SW NW
 CONTR DUKE DRILLING CO CTY ELLIS
 GEOL JERRY J. KNOBEL FIELD DECHANT SO
 E 2021 KB E₂/2/80 CARD 2/5/81 IP SWDW
 2016 GL CM ISSUED ARB OH 3694 $\frac{1}{2}$ -3750
 API 15-051-22,074

SMP	TOPS	DEPTH	DATUM
ANH		1203	+ 818
B ANH		1250	+ 771
TOP		2990	- 969
HEEB		3270	-1249
TOR		3290	-1269
LKC		3316	-1295
B KC		3560	-1539
MARM CHT		3600	-1579
ARB		3634	-1613
RTD		3750	-1729

8-5/8" 292/180sx, 5 $\frac{1}{2}$ " 3694.5/525sx
 NO DST'S
 MICT - CO, (ARB OH), TSTD NAT,
 SWDW - INJECTION RATE SATISFACTORY

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS