

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21277-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 22-22S-15W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SMITH Well #: 1  
County: PAWNEE Total Vertical Depth: 3966 feet

Operator License No.: 3493  
Op Name: FISHER, REGINALD D.  
Address: 110 N. EXCHANGE  
ST. JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3962	2423	WITH 140 SX CMT
SURF	8.625	550		WITH 260 SX CMT #128 90

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/10/2006 12:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3910' WITH 5 SX CMT. 10 SX GEL & 50 SX CMT AT 1000'. 50 SX CMT AT 600'. 20 SX CMT AT 40'.

RECEIVED  
JAN 30 2006

Plugging Proposal Received By: JIM HOLLAND  
Date/Time Plugging Completed: 01/10/2006 2:20 PM

WitnessType: COMPLETE (100%)  
KCC Agent: RICHARD LACEY

KCC WICHITA

Actual Plugging Report:

SANDED BOTTOM TO 3910' & 5 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1023' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 591' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.


Perfs:

Top	Bot	Thru	Comments
3962	3966	OH	

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 1-30-06

INV. NO. 2006061029

Form CE-573