

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20957-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 27-4S-30W  
3004 feet from S Section Line, 1182 feet from E Section Line  
Lease Name: PHILLIPS Well #: 27-2  
County: DECATUR Total Vertical Depth: 4225 feet

Operator License No.: 6861  
Op Name: RON'S OIL OPERATIONS INC  
Address: 1889 200 AVENUE  
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	253		

#137<sup>31</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/24/2006 6:00 AM  
Plug Co. License No.: 33607 Plug Co. Name: KALER OIL COMPANY  
Proposal Revd. from: BOB HORINEK Company: RON'S OIL OPERATIONS, INC. Phone: (785) 421-2315

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES Witness Type: NONE  
Date/Time Plugging Completed: 01/24/2006 7:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

1st. Plug at 2670' w/25 sxs.  
2nd. Plug at 1915' w/100 sxs.  
3rd. Plug at 300' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
JAN 26 2006  
KCC WICHITA

District: 04

Signed Roger A Moses  
(TECHNICIAN)

INVOICED  
DATE 1-26-06  
INV. NO 2006061022

Form CP-2/3

JAN 25 2006