

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21664-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 13-27S-10W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MILBURN A Well #: 1
County: KINGMAN Total Vertical Depth: 4540 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4497		150 SX CMT
SURF	8.625	319		185 SX CMT

\$147⁵⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2005 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING CO., INC. Phone: (620) 234-5191

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 5 sacks of cement. Shot and pulled casing to 1400' and spotted 35 sacks of cement. Pulled casing to 950' and spotted 35 sacks of cement. Pulled casing to 370' and circulated cement to surface with 135 sacks of cement.

60/40 posmix with 4% gel

Copeland Acid & Cementing #30073

Perfs:

Top	Bot	Thru	Comments
4288	4350		

**RECEIVED
KCC DISTRICT #2
DEC 29 2005
WICHITA, KS**

RECEIVED

Remarks:

Plugged through: CSG

**RECEIVED
JAN 26 2006
KCC WICHITA**

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 1-26-06
INV. NO. 2006061021