


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sheridan County. Sec. 3 Twp. 7S Rge. (E) 30 (W)  
Location as "NE/CNW/SW" or footage from lines C SW SE  
Lease Owner King Resources Company  
Lease Name J. M. Huber Well No. 1-3  
Office Address 100 Park Ave. Bldg., Oklahoma City, Okla. 73102  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Dec. 5, 19 68  
Application for plugging filed (phone 12/5/68) Dec. 9, 19 68  
Application for plugging approved Dec. 5, 19 68  
Plugging commenced Dec. 5, 19 68  
Plugging completed Dec. 5, 19 68  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 5000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	344'	8-5/8"	344'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Filled hole with heavy mud to 1650 feet. Spot 70 sacks cement through drill pipe @ 1650 feet. Filled hole with heavy mud to 360 feet. Set plug @ 360' with 20 sacks cement and 1/4 sack hulls. Filled hole with heavy mud to 40 feet. Set plug at 40 feet with 10 sacks cement. Job complete @ 4:45 P.M., December 5, 1968.


RECEIVED  
STATE CORPORATION COMMISSION  
DEC 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
12-11-1968

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall  
830 Sutton Place, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of December, 19 68



My Commission expires Feb. 1, 1972  
Barbara J. Layton, Notary Public.

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

J. M. HUBER #1-3  
 C SW SE Section 3-7S-30W  
 Sheridan County, Kansas

15-179-20164-00-00

Commenced: November 22, 1968  
 Completed: December 5, 1968

OPERATOR - King Resources Company

DEPTH		FORMATION	REMARKS
From	To		
0	70	Surface clay and sand	
70	200	Shale and sand	
200	344	Shale	Ran 11 joints 8-5/8" casing, set @ 344' w/275 sacks cement.
344	1508	Shale	
1508	1940	Shale and sand	
1940	2120	Shale	
2120	2258	Shale and sand	
2258	2368	Sand	
2368	2560	Shale and sand	
2560	2603	Anhydrite	
2603	2720	Shale and red bed	
2720	2880	Shale	
2880	3200	Shale and lime	
3200	3270	Shale	
3270	3330	Lime	
3330	3965	Shale and lime	
3965	4240	Lime	
4240	4515	Lime and shale	
4515	4529	Chert	
4529	4687	Lime and chert	
4687	4720	Lime	
4720	4956	Lime and shale	
4956	5000	Lime	
5000	TD		Dry and abandoned.

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 11 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

12-11-1968

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW SE Section 3-7S-30W, Sheridan County, Kansas to the best of my knowledge and belief.

*E. E. Hall*  
 \_\_\_\_\_  
 E. E. HALL

STATE OF KANSAS        )  
                               ) SS  
 COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 10th day of December, 1968, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

*Barbara J. Layton*  
 \_\_\_\_\_  
 Barbara J. Layton, Notary Public

