


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sheridan County, Sec. 21 Twp. 7 Rge. 30 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Dreiling & Hiko Bell Mining & Oil Company  
Lease Name Gilchrist Well No. 1  
Office Address Route 2, Victoria, Kansas 67671  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed 3-31 19 69  
Application for plugging filed 6-24 19 69  
Application for plugging approved 6-24 19 69  
Plugging commenced 6-28 19 69  
Plugging completed 6-28 19 69  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	348'	None
				4 1/2"	4279.	2176.43

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Loaded hole with 1800# gel at 1700'. Hole circulated. Pulled 4 joints & mixed 100 cubic feet cement 50/50 pozmix with 6% gel. Displaced with 800# gel. Pulled casing to about 375'. Mixed 25 cubic feet cement & displaced with 1 sack gel. Spotted top plug thru 1 joint, 10 cubic feet.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
07-01-1969

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS COUNTY OF ELLIS, ss.  
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leo F. Dreiling*  
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1969

My commission expires September 19, 1970  
JOSEPH A. HESS Notary Public.

