

~~15-179-21500-00-00~~


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County. Sec. 27 Twp. 7 Rge. 30 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE NE

Lease Owner Bass Enterprises Production Company
Lease Name Boggs Well No. 1
Office Address P. O. Box 2760, Midland, Texas 79702
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 3/19/78 19
Application for plugging filed 3/19/78 19
Application for plugging approved 3/19/78 19
Plugging commenced 3/19/78 19
Plugging completed 3/19/78 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4650
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	331	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 1500' with 70 sacks 50/50 poz, 6% gel
Middle Plug at 300' with 20 sacks 50/50 poz, 6% gel
Top & Bridge at 40' with 10 sacks 50/50 Poz, 6% gel
2 sacks in rathole
Job complete at 10 p.m. 3/19/78

RECEIVED
STATE CORPORATION COMMISSION
04-03-1978
APR 03 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
James C. Remsberg (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
200 Douglas Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 1978

Mary Lou Taylor
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



15-179-20500-00

DRILLERS LOG

OPERATOR: Bass Enterprises Production Company
P. O. Box 2760
Midland, Texas 79702

LEASE: Boggs No. 1
C SE NE Sec. 27-7S-30W
Sheridan County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 3/9/78

COMPLETED: 3/20/78

RTD: 4650'

CASING: 8-5/8" set at 331' with 275 sx cement

0' to 337' Sand&Shales (12 1/4" Surface Hole)
337' to 1870' Shale & Shells
1870' to 2051' Sand
2051' to 2115' Shale
2115' to 2300' Shale & Shells
2300' to 2410' Sand
2410' to 2548' Shale
2548' to 2598' Shale & Shells
2598' to 2635' Anhydrite
2635' to 2735' Shale & Shells
2735' to 3410' Shale & Lime
3410' to 4050' Lime & Shale
4050' to 4495' Lime
4495' to 4635' Lime & Shale
4635' to 4650' Lime
4650' RTD

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state that the above and foregoing is a true and correct copy of the No. 1 Boggs log for Bass Enterprises Production Company.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to me this 31st day of March, 1978

RECEIVED
STATE CORPORATION COMMISSION

Mary Lou Taylor
Mary Lou Taylor, Notary

APR 03 1978

CONSERVATION DIVISION
Wichita, Kansas

4/3/78

My commission expires January 17, 1981

