

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD  
15-179-20'218'-00-00

Sheridan County, Sec. 27 Twp. 7 Rge. 30W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Chief Drilling Co., Inc.

Lease Name Yelek Well No. #1

Office Address Suite 905 Century Plaza, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 8-8-69 19

Application for plugging filed 8-8-69 19

Application for plugging approved 8-8-69 19

Plugging commenced 8-8-69 19

Plugging completed 8-8-69 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nicholson

Producing formation Depth to top Bottom Total Depth of Well 4300 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	362'	8 5/8"		

RECEIVED  
STATE CORPORATION COMMISSION  
08-13-1969  
AUG 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug through drill pipe @ 1700' w/100 sacks cement

Set plug through drill pipe @ 335' w/20 sacks cement

Set plug through drill pipe @ 40' w/10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ~~Bill Nicholson~~

Address ~~Merland, Kansas~~

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jim Robinson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson

Suite 905 Century Plaza, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 1969

Betty Brandt  
Betty Brandt

Notary Public.

My commission expires May 9, 1971



8/13/69 RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 13 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL LOG  
 15-179-20218-00-00

Chief Drilling Co., Inc.  
 905 Century Plaza  
 Wichita, Kansas 67202

#1 YELEK  
 C SW NW Sec. 27-7-30W  
 Sheridan County, Kansas

Contractor: Chief Drilling Co., Inc.

Casing Record: 362' of 8'5/8" set w/225 sacks cement.      Commenced: 8-2-69  
 Completed: 8-8-69

FORMATION	FROM	TO	ELEVATION
Surface clay & rock	0	45	2950 Gr.
Shale, shells, & sand	45	326	2952 D.F.
Shale & sand	326	1350	2955 K.B.
Shale, shells & sand	1350	2107	
Shale, shells & lime	2107	2230	
Shale & shell	2230	2619	
Anhydrite	2619	2657	
Shale & shells	2657	2895	
Shale & lime	2895	3720	
Lime	3720	3870	
Lime & shale	3870	4110	
Lime	4110	4300	
Total depth	4300		

  

FORMATION TOPS	
Anhydrite	2619 + 336
Elmont	3728 - 773
Howard	3762 - 807
Topeka	3817 - 862
Heebner	4008 - 1053
Lansing	4048 - 1093
T.D.	4300 - 1345

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW NW of Section 27-7-30W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*Thomas G. Wesselowski*  
 Thomas G. Wesselowski, V. Pres.

Subscribed and sworn to before me this 12th day of August, 1969.

*Betty Brandt*  
 Betty Brandt, Notary Public

My Commission Expires:  
 May 9, 1971