

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-193-20,109-00-00 <sup>01</sup>

LEASE NAME McCormick

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 3-24

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. \_\_\_ TWP. \_\_\_ RGE. \_\_\_ (E) or (W)

COUNTY Thomas

Date Well Completed 02-04-77

Plugging Commenced 08-05-94

Plugging Completed 08-06-94

LEASE OPERATOR Mustang Oil & Gas Corporation

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202

PHONE#(316) 267-8011 OPERATORS LICENSE NO. 5652

Character of Well WVW EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08-04-94 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Submitted with CP-1 08-04-94

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	490'	None
				5-1/2"	4309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

SEE BACK

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Oil & Gas Corporation\* License No. 5652

Address 100 S. Main, Suite 300, Wichita, KS 67202 \*Allied Cement

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corporation


STATE OF Kansas COUNTY OF Sedgwick, ss.

Wayne L. Brinegar

(Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wayne L. Brinegar

(Address) a/a



AND SWORN TO before me this 8th day of August, 19 94

Patricia A. Reilly  
Notary Public

My Commission Expires: August 11, 1995

8-5-94

TOH w/tbg to 1234'. RU Dialog & perforate 5-1/2" csg @2630' & 1780' w/2 shots each setting. TIH w/tbg to 3430'. RU Allied Cementing. Plug as follows:

Spot 75 sxs 60-40 Poz (10% gel) @3430'

Spot 90 sxs 60-40 Poz (10% gel, 300# hulls) @2450'

Spot 60 sxs 60-40 Poz (10% gel, 200# hulls) @1400'; cement to surface

Pump 75 sxs 60-40 Poz (10% gel) down 8-5/8" casing.

Pump 15 sxs 60-40 Poz (10% gel) down 5-1/2" casing.

Pressure up to 500# & held. SI

8-6-94

Cut-off casing & capped. Well P&A 8-6-94



Subject: McCormick 3-24  
15-193-20109-00-01  
Date: Aug 5-1994

TOH w/ chg to 1234. RU Dialog & perforate 5 1/2 Csg @  
2630 & 1780 w/ 2 shots each settings. TIK w/ chg to  
3430. RU Allied cementing. Plug as follows.

Spot 75 ex 60/40 Pos 10% gel @ 3430.

Spot 90 ex 60/40 Pos 10% gel 300# hulls @ 2450

Spot 60 ex 60/40 Pos 10% gel 200# hulls @ 1400 Cmt to surface.

Pump 75 ex 60/40 Pos 10% gel down 8 5/8.

Pump 15 ex 60/40 Pos 10% gel down 5 1/2. Pressure up to  
500# & held. SI

KCC Authority	Dennis Hamel
Allied Cmt	2702.67
Dialog	127.50
Cheyenne Well	864.00
DeRue Tank	597.69
Supervision	400.00
Well to be cut off & capped	8-6-94
Welding	*200

8/9/94  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS