

15-065-02969-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
RECEIVED
STATE CORPORATION COMMISSION
4-12-1989
APR 12 1989

WELL PLUGGING APPLICATION FORM

(File One Copy)

Well was completed on

CONSERVATION DIVISION
Wichita, Kansas 6/89

API Number 10-10-55 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000
2310' FSL

LEASE/FARM Blazier Unit WELL NO. 101W WELL LOCATION 2310' FWL COUNTY Graham

SEC. 21 TWP. 7S RGE. 25 (N) or (W) Total Depth 3907' PLUG BACK TD 3861'

CHECK ONE:

OIL WELL ☐ GAS WELL ☐ D & A ☐ SWD OR ☒ INJ WELL ☐ DOCKET NO. E-9707

SURFACE CASING SIZE 8 5/8" SET AT 238' CEMENTED WITH 225 SACKS

CASING SIZE 5 1/2" SET AT 3907' CEMENTED WITH 175 SACKS

PERFORATED AT 3720 - 3815' (5 sets)

CONDITION OF WELL: GOOD ☐ POOR ☐ CASING LEAK ☒ JUNK IN HOLE ☐

PROPOSED METHOD OF PLUGGING Procedure is attached for KCC approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? NO

(If not explain.) April 20, 1989

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq
AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. J. D. Hininger PHONE # (913) 674-2182

ADDRESS OXY USA Inc., P. O. Box 38, Hill City, KS 67642

PLUGGING CONTRACTOR Ostrom Well Service Inc. * LICENSE NO. 5680 6/89

ADDRESS RR 1 Box 368, Plainville, KS 67663 PHONE # (913) 434-2707

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

*Anticipated Service Co.

SIGNED: Raymond Hui
(Operator or Agent)

DATE: 4-11-1989

(4)



15-065-02969-00-01

MEMORANDUM
OCCIDENTAL OIL AND GAS

Wichita, Kansas
April 4, 1989

TO: Mr. M. D. Harrison
FROM: Mr. P. W. Pringle
SUBJECT: PLUGGING PROCEDURE..... Blazier Unit #101W
2310' FSL - 2310' FWL
Sec. 21-7S-25W
Graham County, Kansas

Well Data:

8-5/8" csg @ 238' w/225 sx
5-1/2" csg @ 3907' w/175 sx
Csg perforated @ 2180' w/400 sx
Perforations: 3720-3815' (5 sets)
PBSD 3861' Last SLM = 3818'

Shallow Formation Data:

Dakota 1030-1360'
Cheyenne 1380-1670'
Anhydrite 2165-2200'

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1989
4-12-1989
CONSERVATION DIVISION
Wichita, Kansas

1. Prior to plugging, obtain approval of project from the KCC District Office #4, Hays, KS (913) 628-1200.
2. Pull well laying down tubes and packer. Run in hole with 2-3/8" workstring to bottom and spot 65/35 Pozmix with 6% gel + hulls to surface. (approximately 346 sx cement)
3. Tie onto the 8-5/8" casing and fill the annulus to surface with the same cement + hulls.
4. Let slurry set 48 hrs, check TOC & cap well.

NOTE: Calculations based on 65/35 Pozmix w/6% gel mixed with 10.9 gals water/sx cement. Slurry yield 1.97 ft³/sx.

PWP/sm

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
JUL 12 1989
EXPIRES

April 12, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

OXY USA, Inc.
P. O. Box 26100
Oklahoma City, OK 73126-0100

Blazier Unit #101W (Inj.)
2310'FSL 2310'FWL
Sec. 21-07S-25W
Graham County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200