

15-065-02971-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1989  
4-25-89  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API Number 12-22-55 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000  
1650' FSL

LEASE/FARM Blazier Unit WELL NO. 103 WELL LOCATION 1650' FWL COUNTY Graham

SEC. 21 TWP. 7S RGE. 25 or (W) Total Depth 3889' PLUG BACK TD 3650'

CHECK ONE:

OIL WELL X GAS WELL      D & A      SWD OR INJ WELL      DOCKET NO.     

SURFACE CASING SIZE 8-5/8" SET AT 238' CEMENTED WITH 225 SACKS

CASING SIZE 5-1/2" SET AT 3889' CEMENTED WITH 175 SACKS

PERFORATED AT 3690-3855' (7 sets)

CONDITION OF WELL: GOOD      POOR      CASING LEAK X JUNK IN HOLE     

PROPOSED METHOD OF PLUGGING Plugging procedure is attached for KCC review and approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? NO  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: 4-30-89\*

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. J. D. Hininger PHONE # (913) 674-2182

ADDRESS OXY USA Inc., P. O. Box 38, Hill City, KS 67642

PLUGGING CONTRACTOR Halliburton Services\*\* LICENSE NO.     

ADDRESS P. O. Box 47, Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Raymond Hill  
(Operator or Agent)

\*Approximate Date  
\*\* Anticipated Service Co.

DATE: 4-24-1989



MEMORANDUM

OCCIDENTAL OIL AND GAS

15-065-02971-00-00

Wichita, Kansas  
April 19, 1989

TO: Mr. M. D. Harrison  
FROM: Mr. P. W. Pringle  
SUBJECT: Plugging Procedure..... Blazier Unit #103  
1650' FSL - 1650' FWL  
Sec 21-7S-25W  
Graham County, Kansas

Well Specs:

8-5/8" Csg @ 238' w/225 sx  
5-1/2" Csg @ 3889' w/175 sx  
DV Tool @ 2184' w/475 sx (cem circ.)  
Perforations 3690-3855' (7 sets)  
CIBP @ 3650'  
(Rough csg from 2700-3739')

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1989

4-25-89

CONSERVATION DIVISION  
Wichita, Kansas

Shallow Formation Data:

Dakota 1020-1360'  
Cheyenne 1380-1670'  
Anhydrite 2165-2200'

- 
1. Prior to plugging, obtain approval of project from the KCC District Office #4, Hays, KS (913) 628-1200.
  2. Tie onto the 5-1/2" casing, establish rate and fill the long pipe to surface with 65/35 Pozmix w/6% gel + hulls. (Approx. 330 sx cement)
  3. Let cement set 48 hrs, check TOC & cap well.

NOTE: Calculations based on 65/35 cement w/6% gel mixed with 10.9 gals water/sx cement. Slurry volume 1.97 ft<sup>3</sup>/sx.



15-065-02971-00-00

Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

THIS NOTICE  
JUL 25 1989  
EXPIRES

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

April 25, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

OXY USA, Inc.  
P. O. Box 26100  
Oklahoma City, OK 73126-0100

Blazier Unit #103  
1650' FSL 1650' FWL  
Sec. 21-07S-25W  
Graham County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht  
Director

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200