

15-069-20234-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Graham County. Sec. 20 Twp. 7S Rge. (E) 25 (W)

Location as "NE/CNW%SW%" or footage from lines SE NE NE

Lease Owner Tilco, et al

Lease Name Clark Well No. 1

Office Address 200 Sutton Place

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-25 19 69

Application for plugging filed 6-25 19 69

Application for plugging approved 6-25 19 69

Plugging commenced 6-25 19 69

Plugging completed 6-25 19 69

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	330	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Plug with 100 sacks cement @ 1275
- Plug with 20 sacks cement @ 360'
- Plug with 10 sacks cement @ 40'

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc. 7-3-69
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 69

My commission expires April 1, 1971

(Address) _____
Glaude Nichols
Notary Public.

15-065-20234-00-00

DRILLER'S LOG

COMPANY	Tilco, et al
CONTRACTOR	LEBEN DRILLING, INC.
FARM	CLARK #1
LOGATION	SE NE NE SECTION 20-7S-25W
	GRAHAM COUNTY, KANSAS
COMMENCED	6-19-69
COMPLETED	6-25-69

0	30	Clay
30	280	Sand, Shale
280	720	Shale
720	1455	Shale, Sand
1455	2110	Shale
2110	2168	Shale, Red Bed
2168	2202	Anhydrite
2202	2700	Shale
2700	3065	Shale, Lime
3065	3185	Lime
3185	3279	Lime, Shale
3279	3610	Shale, Lime
3610	3720	Lime, Shale
3720	3905	Lime
3905	3920	Lime, Shale
	<u>3920</u>	<u>RTD - D. & A.</u>

8 5/8" 20# new surface casing set @ 330' cemented with 225 sacks Common cement 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Clark #1 Well located SE NE NE of Section 20, Township 7 South, Range 25 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in 7-3-69
and for Barton County, Kansas, this 1st day of July, 1969.

Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1971