

15-065-02962-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 22 TWP. 7S RGE. 25 ~~XX~~W
Location as in quarters or footage from lines:
990' S - 330' E of Center ~~SE~~ SW NW SE

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate Well
correctly on above
Section Platt.

Lease Owner Cities Service Company
Lease Name Blazier LKC Unit Well No. 202
Office Address 209 E. William, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed September 2, 1955
Application for plugging filed March 22, 1982
Plugging commenced June 10, 1982
Plugging completed June 10, 1982

Reason for abandonment of well or producing formation
Bad casing in the well.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Lansing - KC Depth to top 3745' bottom 3843' T.D. 3890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 238' | -0- |
| | | | | 5 1/2" | 3890' | -0- |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Ran 1275' of 2" tubing, cement with 190 sacks 50-50 Pozmix plus 6% gel plus
3% CaCl plus 5 sacks hulls. Cement circulated. Pulled tubing. Plug and
abandon completed June 10, 1982.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles E. Forrester (employee of owner) or ~~owner or operator~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Charles E. Forrester
Charles E. Forrester
(Address)

209 E. William, Wichita, KS 67202
day of July, 19 82

JACQUELINE PIERCE
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1982
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 2

2-27-85

My Commission expires: 2/27/85

Jacqueline Pierce
Jacqueline Pierce - Notary Public.