

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
Address: 100 S. Main, Suite 200
Phone: (316) 262-3596 Operator License #: 9408
Type of Well: ENHR Docket #: E-16,442
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 1/13/2006 (Date)
by: Greg Eaves (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: 2836' Bottom: 2849' T.D. _____
_____ Depth to Top: 2452' Bottom: 2456' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-053-20127-00-01
Lease Name: A. Soukup
Well Number: #1
Spot Location (QQQQ): _____ - SW - SW - SW
330 Feet from North / South Section Line
4950 Feet from East / West Section Line
Sec. 16 Twp. 14 S. R. 10 East West
County: Ellsworth
Date Well Completed: 1/23/2006
Plugging Commenced: 1/23/2006
Plugging Completed: 1/23/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	253'	8-5/8"		
		Surface	2975'	4-1/2"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Klima Well SVS. moved to location, released Pkr, pulled 89 jts Duo lined tbg and pkr. Sanded off perms w/43 sxs river sand.
Perf Tech found sand @ 2000'. Place 4 sxs cement on sand w/dump bailer. Perf @ 1250' w/2 shts, 900' w/2 shts, 305' w/2 shts.
Allied Cement cemented @ 1250' w/35 sxs 60/40 pozmix, 4% gel, 35 sxs @ 900', circulate from 305' w/40 sxs 60/40 4% gel,
cemented 4 1/2 and 8 5/8 csg w/65 sxs 60/40. Ellsworth Redi-Mix topped csg and surface pipe w/2 yds cement slurry.


Name of Plugging Contractor: Allied Cementing Co., Inc. Klima Well SVS License #: #7023
Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation
State of Kansas County, Sedgwick, ss. _____
Gary Sharp

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Sharp
(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 26th day of January, 2006
Glenna E. Lowe My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bern

ALLIED CEMENTING CO., INC. 18724

Federal Tax I.D.# XXXXXXXXXX

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

DATE <u>1/16/06</u>	SEC. <u>16</u>	TWP. <u>14</u>	RANGE <u>10</u>	CALLED OUT	CN LOCATION <u>11:00 A.M.</u>	JOB START	JOB FINISH <u>12:30 P.M.</u>
LEASE <u>Soukup</u>		WELL # <u>2</u>		LOCATION <u>WELSON LN 40 RD. D</u>		COUNTY <u>EUSSAULT</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1E N INTO</u>			

CONTRACTOR KEEMA

TYPE OF JOB ONP

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH _____

TUBING SIZE 2 DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT

AMOUNT ORDERED 200 10740 490 GEL

500# HULLS

USED 175 2x + 2 Hulls

COMMON	<u>105</u>	@	<u>870</u>	<u>913 50</u>
POZMIX	<u>70</u>	@	<u>470</u>	<u>329 00</u>
GEL	<u>7</u>	@	<u>14 00</u>	<u>98 00</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>1</u>	@	<u>21 00</u>	<u>21 00</u>

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 27 2006
CONSERVATION DIVISION
WICHITA, KS

HANDLING	<u>213</u>	@	<u>165</u>	<u>340 00</u>
MILEAGE	<u>6 1/2</u>	@	<u>SK/mile</u>	<u>293 94</u>
				TOTAL <u>1996 24</u>

EQUIPMENT

PUMP TRUCK CEMENTER PAUL

316 HELPER CLEV

BULK TRUCK

378 DRIVER BRAIN

BULK TRUCK

_____ DRIVER _____

REMARKS:

35 2x - 1200'

35 2x - 900'

305' - CIRCULATE CEMENT

w/ 40 2x

4 1/2 2x - Mix 100x w/ 1 Hull,

Circulating CEMENT BETWEEN

4 1/2 & 8 5/8" TO SURFACE

CHARGE TO: TRANS-PAC

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 600 00

EXTRA FOOTAGE _____ @ _____

MILEAGE 23 @ 5 00 115 00

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 715 00

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Frank Bink

PRINTED NAME