

STATE OF KANSAS
STATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-053-21,177-0000

LEASE NAME Lange "A"

WELL NUMBER 1-30

2,310 Ft. from S Section Line

2,250 Ft. from E Section Line

SEC. 30 TWP. 14 RGE. 9 ~~W~~ (W)

COUNTY Ellsworth

Date Well Completed 1-17-06

Plugging Commenced 1-17-06

Plugging Completed 1-17-06

RECEIVED

JAN 26 2006

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 100 S. Main, Ste 200, Wichita, KS 67202

PHONE#(316) 262-2596 OPERATORS LICENSE NO. 9408

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-16-06 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,236'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	340'	Cmtd. w/250 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Push bridge plug to 3,185', spot 35 sax cement on plug; push bridge plug to 1,250', spot 35 sax cement on plug; push bridge plug to 800', spot 35 sax cement on plug; push bridge plug to 390', spot 35 sax cement on plug; push wiper plug to 60', dump 25 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Jack P. Beeman, Sec.-Treas. Contractor (Employee of ~~XXXXXXXXXX~~) or ~~XXXXXXXXXX~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 2006

My Commission Expires:  5-26-07
Notary Public Beuth Phillips




Shields

Russell, Kansas

WELL LOG

Operator: Trans Pacific Oil Corporation
 Well: Lange "A" #1-30
 Commenced: January 9, 2006
 Completed: January 17, 2006
 Contractor: Shields Drilling Co.

Well Description: 2,310' FSL, 2,250' FEL,
 SE/4 Sec. 30-14S-9W
 Ellsworth Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	340'	Cmtd. w/250 sax

Elevation: 1,624' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Surface clay, sand, shale	190'	
Shale & sand	343'	
Redbed	410'	
Anhydrite	450'	
Redbed & shale	775'	
Shale	2,325'	
Lime	3,185'	
Arbuckle	3,236'	RTD

RECEIVED
 JAN 26 2006
 KCC WICHITA

Notes