

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED SEP 07 2005 KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior, Inc.

Address: P.O. Box 399

Phone: (785) 398-2270 Operator License #: 4058

Type of Well: SWD Docket #: D-19,218 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/31/05 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Cedar Hill Depth to Top: 810 Bottom: 870 T.D. 1359

API Number: 15-083-20549-00-00

Lease Name: Housman

Well Number: 2

Spot Location (QQQQ): 150' E - NW - NE -

660 Feet from North / South Section Line

810 Feet from East / West Section Line

Sec. 9 Twp. 23 S. R. 22 East West

County: Hodgeman

Date Well Completed: 9/14/77

Plugging Commenced: 8/31/05

Plugging Completed: 8/31/05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Cedar Hill, water, 810, 870, 8 5/8", 424', None. Row 2: 5 1/2", 1359', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mix 100 sacks of 60/40 poz with 6% gel and 400# of hulls, pump down 5 1/2" casing. Hole stayed full and pressured to 400 psi and held. Pumped 10 sacks down 8 5/8" braden head and pressured up to 500 psi and held. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: N. Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Corsair

(Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 2nd day of September, 20 05

Bernice Moore Notary Public My Commission Expires: 2/7/06



Handwritten initials 'Bu'