

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
RECEIVED  
STATE CORPORATION COMMISSION  
89

APR 12 1989  
4-12-1989  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
(File One Copy)

Well was completed on

API Number 01-17-56 (of this well). (This must be listed, if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000  
990' FNL

LEASE/FARM Blazier Unit WELL NO. 401W WELL LOCATION 330' FWL COUNTY Graham

SEC. 27 TWP. 7S RGE. 25 (A) or (W) Total Depth 3900' PLUG BACK TD 3871'

CHECK ONE:

OIL WELL  GAS WELL  D & A  SWD OR  INJ WELL  DOCKET NO. E-9707

SURFACE CASING SIZE 8-5/8" SET AT 235' CEMENTED WITH 225 SACKS

CASING SIZE 4-1/2" SET AT 3884' CEMENTED WITH 200 SACKS

PERFORATED AT 3689 - 3789' (4 sets)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Procedure is attached for KCC approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? NO  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: April 20, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. J. D. Hininger PHONE # (913) 674-2182

ADDRESS OXY USA Inc., P. O. Box 38, Hill City, KS 67642

PLUGGING CONTRACTOR Ostrom Well Service Inc. \* LICENSE NO. 5680

ADDRESS RR 1 Box 368, Plainville, KS 67663 PHONE # (913) 434-2707

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

\*Anticipated Service Co.

SIGNED: Raymond Hui  
(Operator or Agent)

DATE: 4-11-1989



MEMORANDUM  
OCCIDENTAL OIL AND GAS

Wichita, Kansas  
April 4, 1989

TO: Mr. M. D. Harrison  
FROM: Mr. P. W. Pringle  
SUBJECT: PLUGGING PROCEDURE..... Blazier Unit #401W  
990' FNL - 330' FWL  
Sec. 27-7S-25W  
Graham County, Kansas

Well Data:

8-5/8" csg @ 235' w/225 sx  
4-1/2" csg @ 3884' w/200 sx  
DV Tool @ 2141' w/500 sx (TOC 625')  
Perforations: 3689-3789' (4 sets)  
PBSD 3871'

RECEIVED  
STATE CORPORATION COMMISSION

APR 12 1989  
4-12-1989  
CONSERVATION DIVISION  
Wichita, Kansas

Shallow Formation Data:

Dakota 1015-1320'  
Cheyenne 1340-1635'  
Anhydrite 2125-60'

- 
1. Prior to plugging, obtain approval of project from the KCC District Office #4, Hays, KS (913) 628-1200.
  2. Pull tubes and packer. Run in hole with 2-3/8" workstring to bottom and spot 65/35 Pozmix with 6% gel + hulls to surface. (approximately 233 sx cement)
  3. Tie onto the 8-5/8" casing and fill the annulus to surface with 100 sx same cement + hulls.
  4. Let cement set 48 hrs, check TOC & cap well.

NOTE: Calculations based on 65/35 Pozmix w/6% gel mixed with 10.9 gals water/sx cement. Slurry yield 1.97 ft<sup>3</sup>/sx.

PWP/sm

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
MARGALEE WRIGHT COMMISSIONER  
JUDITH McCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE  
JUL 12 1989  
EXPIRES

April 12, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

OXY USA, Inc.  
P. O. Box 26100  
Oklahoma City, OK 73126-0100

Blazier Unit #401W (Inj.)  
990'FNL 330'FWL  
Sec. 27-07S-25W  
Graham County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200