

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15-193-20195-00-02 (of this well)

Lease Owner A. L. Abercrombie, Inc.

Address 801 Union Center, Wichita, Kansas 67202

Lease (Farm Name) HOFFNER "A"

Well No. 1

Well Location SW NW Sec. 22 Twp. 7S Rge. 36W (E) (W) X

County Thomas Total Depth 4940' Field Name \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A \_\_\_\_\_

Well Log attached with this application as required Yes

Date and hour plugging is desired to begin Approximately October 8, 1980 at 10:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

G. W. Sowles

A. L. Abercrombie, Inc. Rt. #1 Box 56  
Address Great Bend, Kansas 67530

Plugging Contractor A. L. Abercrombie, Inc.

License No. \_\_\_\_\_

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name A. L. Abercrombie, Inc.

Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: \_\_\_\_\_

G. W. Sowles  
Applicant or Acting Agent

G. W. Sowles, Vice President

Date: October 2, 1980

RECEIVED  
STATE CORPORATION COMMISSION  
OCT - 9 1980  
CONSERVATION DIVISION  
Wichita, Kansas  
10/9/80

State of Kansas



15-193-20195-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

October 14, 1980

WELL PLUGGING AUTHORITY

Hoffner "A" #1  
SW NW, Sec. 22-7S-36W  
Thomas County  
4940'  
A.L. Abercrombie, Inc.


A.L. Abercrombie, Inc.  
801 Union Center  
Wichita, KS 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,

  
For Administrator

Mr. Gilbert Balthazor, Box 9, Palco, KS 67657  
is hereby assigned to supervise the plugging of the above named well.

To Gois

KANSAS DRILLERS LOG

S. 22 T. 7S R. 36W<sup>E</sup><sub>W</sub>  
Loc. 2200' from NL, 2200' from EL  
County Thomas N

API No. 15 — 193 — 20,195-50-80  
County Number

Operator  
Abercrombie Drilling, Inc.

Address  
801 Union Center, Wichita, Kansas 67202


Well No. 1 Lease Name Hoffner "A"

Footage Location  
2200' feet from (N) line 2200' feet from (E) line

Principal Contractor Abercrombie Drilling, Inc Geologist Bill Darrow

Spud Date November 06, 1979 Total Depth 4940' P.B.T.D. 1078'

Date Completed 8-12-80 Oil Purchaser None



Elev.: Gr. 3383'  
DF 3386' KB 3388'

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	20#	409'	60/40 posmix	225	3% Ca.Cl. 2% gel.
Production	7-7/8"	4-1/2"	9-1/2	1119'	50/50 posmix Common	400 75	6% gel. 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	DP Jets.	821-828

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac w/ 9500 gal. & 10,000# sand (20/40) 46000 SCF Nitrogen	821-828

INITIAL PRODUCTION

Date of first production None	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Producing interval (ft.)	
		Trace	6	821-828	
Disposition of gas (vented, used on lease or sold)			Producing interval (ft.)		

RECEIVED 10/9/80  
STATE CORPORATION COMMISSION  
OCT - 9 1980  
CONSERVATION DIVISION  
Wichita, Kansas

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 67217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator McDermott Drilling, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: D & A

Well No. 1 Lease Name Hoffner "A" 15-193-20195-00-00

S 22 T 7SR 36 E W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface soil and sand	0	194	SAMPLE TOPS	
Clay sand and shale	194	410	Anhydrite	2994' (+ 390)
Shale	410	2000	B/Anhydrite	3032' (+ 350)
Shale, sand and lime	2000	2390	Heebner	4195' (- 807)
Shale and sand	2390	3044	Toronto	4230' (- 842)
Shale and lime	3044	3200	Lansing	4248' (- 860)
Lime and shale	3200	3960	Ft. Scott	4661' (-1273)
Lime	3960	4940	Cherokee	4693' (-1305)
Rotary Total Depth		4940		

DST #1 (4211-4260') 30", 45", 60", 45"  
 Rec. 90' mw.  
 IFP 54-65, IBHP 1264, FFP 76-98, FBHP 1212.

DST #2 (4399-4435') 30", 45", 30", 30"  
 Rec. 30' mud.  
 IFP 43-43, IBHP 76, FFP 54-54, FBHP 65.

DST #3 (4440-4508') 30", 45", 30", 30"  
 Rec. 65' socm.  
 IFP 65-76, IBHP 1243, FFP 87-98, FBHP 1107.

DST #4 (4542-4594') 30", 45", 30", 30"  
 Rec. 30' mud.  
 IFP 54-54, IBHP 87, FFP 54-65, FBHP 76.

ELECTRIC LOG TOPS:

Anhydrite	2990' (+ 390)
B/Anhydrite	3026' (+ 362)
Heebner	4192' (- 804)
Toronto	4226' (- 838)
Lansing	4246' (- 858)
Stark	4442' (-1054)
B/KC	4532' (-1144)
Marmaton	4554' (-1166)
Ft. Scott	4660' (-1272)
Cherokee	4688' (-1300)
Miss.	4908' (-1520)
LTD	4937'
RTD	4940'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD

RECEIVED 10/9/80  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 OCT - 9 1980

Date Received	Signature <u>Carl J. ...</u>
	Title <u>...</u>
	Date <u>June 12, 1980</u>