

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-179-20,883 -00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Scarth Oil & Gas Company OPERATORS LICENSE NO. 9826

ADDRESS 901 S. Polk, Amarillo, TX 79101 PHONE # (806) 373-6932

LEASE (FARM) Barnett WELL NO. 1 WELL LOCATION C SE NE COUNTY Sheridan

SEC. 24 TWP. 7 RGE. 26 (~~XXX~~ (W) TOTAL DEPTH 4100' PLUG BACK TO

Check One:

OIL WELL  GAS WELL  D & A X SWD or INJ WELL  DOCKET NO.

SURFACE CASING SIZE 8-5/8 SET AT 307 CEMENTED WITH 210 SACKS

CASING SIZE  SET AT  CEMENTED WITH  SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug at 2280'-25 sacks; 2nd plug at 1420'-100  
sacks and 1 sack floseal; 3rd plug at 350'-40 sacks; 4 th plug at 40' to solid bridge-10 sacks; rathole-15 sacks;  
all cement 60/40 posmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? no  
(If not, explain)  Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11:00 a.m. 1-5-87

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642 STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422 JAN 19 1987

ADDRESS 801 union Center, Wichita, KS 67202 PHONE # (316) 262-1841 CONSERVATION DIVISION  
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton

(Operator or Agent)  
Jack K. Wharton, Secy/Treas

DATE: 1-9-87