

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00297-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 50-42

LOCATION SW SW SW

SEC. 9 TWP. 7 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Anderson

Operator Francis Oil & Gas Address 905 Palace Bldg Tulsa,

Field _____ County Rooks

Total Depth 3408 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 220' circulated with cement - 5 1/2" at 3399' with
12s sax cement behind.

Filled with sand to 3390', set 4 sax cement with dump bailer,

Pumped in 12 sax mud, 70 saxmud with 20 sax hulls and 40 sax

mud with 2 bales Palce Seal - pulled approx 900' 5 1/2" - set

plug at 220' with rock bridge and 15 sax cement - mud to

35', set rock and 10 sax cement to bottom cellar.

PLUGGING
WELL SEC 9 T 7 R 19
BOOK PAGE 50 LINE 42

11-11-52
RECEIVED
STATE CORPORATION COMMISSION

NOV 11 1952

CONSERVATION DIVISION
WICHITA, KANSAS

District Conservation Agent

Date 11-5-52