

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 163-21,473 <sup>500</sup> 00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name T.X.O. PRODUCTION CORPORATION

Complete Address 200 WEST DOUGLAS, #300 WICHITA, KANSAS, 67202

Lease Name DRYDEN Well-No. #3

Location 330' FEL-1650 FSL <sup>SE 1/4 E 8L</sup> Sec. 8 Twp. 7 Rge. 19 (East)(West)

County ROOFS. Total Depth 3470 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor MURFIN DRILLING CO. (LOYD BELLETT)

Address 617 UNION STR. BLDG. WICHITA, MO. License No. \_\_\_\_\_

Operation Completed: Hour: 7:00 PM Day: 12<sup>th</sup> Month: NOV. Year: 1981

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" 259' 50. CUL w/ 175' QUICK SET - 2% GEL - 3% CA-CL.  
ORDERED 130' 50/50 FORMIL 4% GEL - 3% CA-CL. + 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.  
1<sup>st</sup> Plug. @ 870' FE w/ 70' 50" CNT.  
2<sup>nd</sup> Plug. @ 240' FE w/ 40' 50" CNT.  
3<sup>rd</sup> Plug. → SOLID BRIDGE @ 40' 1/2" w/ 10' 50" CNT.  
10' 50" IN RAT HOLE.

CEMENTED BY SUN CMA.

**INVOICED**

RECEIVED  
STATE CORPORATION COMMISSION  
11-20-81  
NOV 20 1981

I hereby certify that the above plugging instructions were given as herein stated.  
Signed: Marion Schmidt  
Conservation Division Agent

DATE 12-21-81

INV. NO. 28506w CONSERVATION DIVISION  
Wichita, Kansas