

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-103-00223-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1962
6-8-62
CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: _____ Rooks

Location: NE NE NW Sec. 8 Twp. 7 Rge. _____ (E) _____ (W) 19

Name of Field: Griebel Total Depth: 3456

I have this date completed supervision of plugging of:

Lease Name: Griebel Well No. 1

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Ralph Lynch

Address: Great Bend, Kansas License No. 457

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 5 Month 6 Year 62

The above well was plugged as follows:

8 5/8" 216' circulated with cement - 5 1/2" 3454' with 100 sax cement,
Perf 3164' - set cementing plug at 3150' - 50' sand and 4 sax cement set
with dump bailer - pulled 1008' 5 1/2" to 550', circulated hole with heavy
mud at 550' (20 sax Gel & 5 Sax hulls) - displaced 20 sax cement through
5 1/2" at 550', heavy mud to 180', - displaced 20 sax cement through 5 1/2" at 180',
heavy mud to 35', set bridge and cement to bottom collar.

Signed: Edon Kelly
Conservation Division Agent

Reviewed: Harold J. Davis
Field Supervisor

Remarks:

INVOICED
DATE 6/12/62
INV. NO. 5154-w