

DISTRICT CONSERVATION AGENT'S REPORT

15-065-03319-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CE 1/2 NE NE

SEC. 22 TWP. 7 RGE. 22 *w*

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease ~~Weisbeck~~ Weissbeck

Operator Jones Shelburn Farmer Address Russell, Kans

Field _____ County Graham

Total Depth 3848 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3845 with

25 sax cement behind, perforated and squeezed with 100
additional sax cement.

Chat to 165' set 4 sax cement, pulled 3000' 5 1/2', filled with

mud to 165' set rock and 15 sax cement, mud to 35', set
rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 22 T 7 R 22
BOOK PAGE 53 LINE 27

RECEIVED
STATE CORPORATION COMMISSION

OCT 20 1952

CONSERVATION DIVISION
Wichita, Kansas

10-20-52

Edwin Petty
District Conservation Agent
Date 10-18-52