

KANSAS

4 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20587-00-00

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1973

CONSERVATION DIVISION
Wichita, Kansas

2-5-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Oil Company,
SUITE 550 - 200 W. DOUGLAS
Complete Address Garvey Building, Wichita, Kansas.

Lease Name Korb Well No. 1

Location CSE-SW Sec. 27 Twp. 7 Rge. (E) (W) 22

County Graham Total Depth 3802'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 11:00 PM Day 1 Month 2 Year 1973

The above well was plugged as follows:

265'---8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 625'.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 105 Cu. Ft. cement
thru DP from 850' to 525'. Pulled DP to 270' and displaced 30 Cu. Ft. cement thru
DP from 270' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. Z. Richards
Well Plugging Supervisor

DATE 2/5/73
INV. NO. 6941-W