



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-005-00100-00-01

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas

2-14-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Charles L. Carlock.

Complete Address 1515 Hillcrest, Newton, Kansas.

Lease Name DePrad Well No. 1

Location NW-NE Sec. 27 Twp. 7 Rge. (E) (W) 22

County Graham Total Depth 3777'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling, Incorporated.

Address Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 12:30 PM Day 3 Month 7 Year 1969

The above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 260 Sx.

3770'--1 1/2" Production casing cemented on bottom with 220 Sx.--(Top of cement @ 3000'--Temp. Survey). Well plugged back to 3600'. Top perforations @ 3450'.

Pushed plug to 3300', built sand bridge to 3280' and set 3 Sx. cement with dump bailer.

Pulled 1 1/2" casing and squeezed well with initially 5 sacks hulls and 19 sacks gel then

100 Sx. cement from 850' to 525' then 8 sacks gel from 525' to 205' and followed with

20 Sx. cement from 205' to 145' then 3 sacks gel from 145' to 30' and finally 10 Sx.

cement from 30' to bottom of cellar. Max. pump-in pressure--300#. Final shut-in press-

ure--200#. (Recovered 2335'--1 1/2" casing). Mudding and cementing by Allied Cementing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dicks
Well Plugging Supervisor

DATE 7/14/69

INV. NO. 81-4