

KANSAS

Form CP-3  
Rev. 6-4-68

9

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20291-06-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
12-24-69

Operator's Full Name Delbert Worcester,  
Complete Address Hill City, Kansas. (09) 642  
Lease Name Worcester Well No. 3  
Location SW-NE-NW Sec. 23 Twp. 7 Rge. (E) (W) 22  
County Graham Total Depth 3800'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Helberg Oil Company,  
Address Morland, Kansas. License No.         
Operation Completed: Hour 3:00 PM Day 18 Month 12 Year 1969

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 135 Sx.  
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru  
DP from 900' to 575'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Diehl  
Well Plugging Supervisor

INVOICED

DATE 12-24-69  
INV. NO. 1136-W