

DISTRICT CONSERVATION AGENT'S REPORT

R

15-065-19041-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NW

SEC. 23 TWP. 7 RGE. 22 *W*

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Worcester

Operator V. D. Sidey Address Russell, Kans

Field _____ County Graham

Total Depth 3819 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 110' circulated with cement - 5 1/2" at 3791' with

100 sax cement behind - perforated at 3649'.

Filled with sand to 3780', set 3 sax cement with dump bailer.

Filled with sand to 3640', set 3 sax cement with dump bailer.

Pumped 1500' 5 1/2" - pumped 30 sax commercial mud in hole

through 5 1/2" - mud to 190', set rock and 15 sax cement at 190',

mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1955

CONSERVATION DIVISION
Wichita, Kansas

4-4-55

John T. ...
District Conservation Agent

DATE 5-29-55

PLUGGING
FILE SEC 23 TWP. 7 RGE. 22 W
BOOK PAGE 108 LINE 39