


15-065-00875-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 23 Twp. 7 Rge. 25 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner C-G DRILLING CO. & N. APPLEMAN CO.
Lease Name LINDENMAN Well No. I
Office Address 107 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed January 21 19 56
Application for plugging filed January 21 19 56
Application for plugging approved January 21 19 56
Plugging commenced January 21 19 56
Plugging completed January 21 19 56
Reason for abandonment of well or producing formation Too low structurally



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 185'. Set plug. Put in 1/2 sack hulls and 15 sacks of cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

1-27-56

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. GALLOWAY (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 56

My commission expires May 20, 1959

Vicky Jacobs
Vicky Jacobs
Notary Public.

PLUGGING
FILE SEC 23 T 7 R 25w
BOOK PAGE 33 LINE 5

15-065-00875-00-00

CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. & N. APPLEMAN CO. WELL NAME LINDENMAN #1

LOCATION SW SW SE Sec. 23-7S-25W RIG NO. 2

COUNTY GRAHAM STATE KANSAS

COMMENCEMENT DATE JANUARY 6, 1956 COMPLETION DATE JANUARY 21, 1956

LOG OF WELL

ELEVATION 2542' rotary bushing.
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	85	Sand		
85	192	Shale-Shells		
192	735	Shale		
735	1065	Shale		
1065	1205	Sand-Shale		
1205	1315	Red Bed-Shale		
1315	1575	Shale-Shells		
1575	1650	Shale		
1650	1740	Shale		
1740	1875	Shale-Sand		
1875	2120	Red Bed		
2120	2202	Anhydrite		
2202	2440	Shale-Shells		
2440	2610	Shale-Shells	0° - 2500'	
2610	2760	Shale-Shells	0° - 2750'	
2760	2900	Shale-Shells		
2900	3020	Shale-Shells	0° - 3000'	
3020	3085	Shale-Shells		
3085	3135	Shale-Lime		
3135	3210	Shale-Lime	0° - 3200'	
3210	3380	Shale-Lime		
3380	3450	Shale-Lime		
3450	3525	Shale-Lime	0° - 3500'	
3525	3650	Shale-Lime		
3650	3735	Shale-Lime		
3735	3769	Shale-Lime	0° - 3750'	
3769	3830	Lime		
3830	3872	Shale-Lime		
3872	3950	Lime		
3950	3977	Lime		
3977	3994	Sand		
	3994	TD		

RECORDED
STATE OF KANSAS
JAN 27 1956
1-27-56

CASING LEFT IN HOLE AFTER COMPLETION

195' of 8-5/8" OD Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK ss.

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.


C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

Subscribed and sworn to before me on this 23rd day of January, 1956.

My commission expires May 20, 1959.

Vicky Jacobs
Vicky Jacobs, Notary Public



PLUGGING
FILE SEC 23 T 7 R 25W
BOOK PAGE 33 LINE 5