


15-065-00628-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec 26 Twp 7 Rge. 25 1/4 W (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Woodman & Iannitti and E. J. Carter
Lease Name Moore Well No. 1
Office Address P. O. Box 387, Heisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-12 1958
Application for plugging filed 12-12 1958
Application for plugging approved 12-12 1958
Plugging commenced 12-12 1958
Plugging completed 12-12 1958
Reason for abandonment of well or producing formation Dry.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4005 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug 600 - 20 sacks
Middle plug 180 - 20 sacks
Top Plug 40 - 10 sacks

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1958
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Woodman & Iannitti Drilling Company
Address P. O. Box 387, Heisington, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. T. Woodman (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman
714 Union National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 58

My commission expires March 15, 1961
Mildred C. Lick
Notary Public.

PLUGGING
FILE SEC 26 T. 7 R. 25W
BOOK PAGE 4 LINE 38

DRILLING LOG

Company: Woodman & Iannitti and E. J. Carter
 Lease: #1 MOORE - SE SE SW Sec. 26-7-25W
 Graham County, Kansas
 Contractor: Woodman & Iannitti Drilling Company
 P. O. Box 387, Hoisington, Kansas
 Date Commenced: 12-3-58
 Date Completed: 12-12-58
 Total Depth: 4005'
 Casing: 8 5/8" set at 280' with 170 sacks

Figures Indicate the Bottom of Formation

0-40	Clay	2625	Shale
150	Sand	2770	Broken Lime, Shale
180	Shale	2890	Lime
505	Shale & Sand	3005	Lime & Shale
1100	Shale	3170	Lime & Shale
1300	Sand, Pink Shale	3205	Lime
1760	Shale & Sand	3270	Lime & Shale
2180	Shale & Shells	3485	Lime
2195	Red Bed	3575	Lime & Shale
2225	Anhydrite	3991	Lime
2500	Shale & Shells	4005	Shale

GEOLOGICAL TOPS

Elevation	2512 RB
Anhydrite	2195 / 317
Heebner	3731 -1219
Toronto	3754 -1242
Lansing	3772 -1260
Base/Kansas City	3785 -1273
Total Depth	4005 -1493

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
 K. T. WOODMAN

12-17-58
RECEIVED
 STATE CORPORATION COMMISSION
 DEC 17 1958
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 26 T 1 R 25W
 BOOK PAGE 4 LINE 38